TROJAN HORSE ARENA

Hazel Green Regional Athletic Complex

Hazel Green area, Madison County, Alabama (site TBD, D-006)

PHASE 2 — SCHEMATIC SET · REV E

Current design: P2-A-101 Rev N / A-102 Rev I, SRM look (A-201 Rev L, A-901 Rev G)

PROJECT DATA

Building	86,964 GSF = L1 57,896 + L2 29,068 (unchanged since A-101 Rev M)
Seats	2,200 (1,100 telescopic + 1,100 fixed); event floor chairs-only design case (D-054)
Exits	E1 (8 pairs, 512 in) + X1-X11; 4 stairs x 76 in; ST-2 in a 30 ft drum (D-082)
Heights	L2 FF 17'-9" (D-061); ring roof 32.75', arena roof 42' (ASSUMED)
Code basis	IBC 2021 (ASSUMED edition); AHJ Madison County / State of Alabama TBD (D-008)
Status	PRELIMINARY — conceptual design, not for construction or permit

CONTACT

Shane Brazelton

256-508-4608

brazeltonshane@gmail.com

GENERAL NOTES: Drawn by KEYSTONE (AI) for Shane Brazelton. Every value not cited is ASSUMED. A licensed architect and engineers must design, check and seal the work; the AHJ decides code questions (D-008). Supersedes the Set Rev D cover (G-001 Rev C).

SHEET INDEX — PHASE 2 SET REV E (current revisions only)

SHEET	TITLE	REV	BASIS
P2-G-001	Cover sheet + sheet index	D	this sheet
P2-G-002	Code analysis — exit recheck	F	egress on A-101 N / A-102 I
P2-G-003	Program test-fit + areas	N	D-086
P2-C-101	Site plan — campus diagram	H	no bus loop (D-087)
P2-A-101	Overall floor plan — Level 1	N	D-082..D-086
P2-A-102	Overall floor plan — Level 2	I	D-082, D-083, D-085
P2-A-103	Floor overlays — mats, seating, conversions	D	Set Rev D (D-073)
P2-A-111	Life safety plan — Levels 1 + 2	E	X1-X11, travel, discharge
P2-A-201	Exterior elevations — SRM look	L	D-074
P2-A-301	Building sections	E	drum + SRM bands
P2-A-302	Sight-line study	C	bowl only; unchanged
P2-A-401	Enlarged plans — lockers + core 2	D	cores = D-072 = D-084
P2-A-901	3D massing — SRM look	G	D-074, no bus loop
APPENDIX — STUDY SHEETS (for decisions, not revisions of the set)			
P2-SK-01	Study: mech / elec bay height	—	PENDING Shane / architect
P2-SK-02	Study: NE drum height	—	PENDING Shane / architect

Not current and not in this set: G-001 A-C, G-002 A-E, A-101 A-M, A-102 A-H, A-111 A-D, A-201 A-K, A-301 A-D, A-901 A-F, C-101 A-G and Set Rev A-D (archive). The earlier Gemini ARCH D package was superseded and removed.

DESIGN DIRECTION

- D-074 SRM HQ language: board-formed concrete slab-edge bands with continuous glass per level, no square corners (R 20'), 30' concrete drum with glass slots, slender colonnade + canopy at the lobby, crimson portal. Band levels, column spacing 14.5' and canopy 12' ASSUMED.
- D-087 Bus loop CUT. Service stays at the north door S1; team bus / van drop-off curbside on the parking drive aisle (ASSUMED, TBD with the parcel, D-006).
- D-082..D-086: 30' drum for ST-2, drum door, east side = D-072, landing note, old NE strip = MECH (remote).

OPEN DECISIONS

- SK-01 mech / elec bay height: 16' as drawn (= annex), taller (e.g. 24', A) or full height to the 32.75' ring roof. PENDING.
- SK-02 NE drum height: flush with the ring roof as drawn, rising as a tower (e.g. +8', A) or stop at stair / roof-access height. PENDING.
- Mechanical 4.95 % of GSF vs the 5 % target (D-072): 47 SF short; MEP engineer to size. OPEN.
- East-face glazing: the east wall is flush with the 42' arena volume; drawn concrete, no glass (A-201 Rev L, ASSUMED). Glass or not? OPEN.
- Egress findings (G-002 Rev F): colonnade column on the E1 axis; X6 discharge grading at the NE corner. Options on G-002 Rev F.
- Parcel (D-006), parking ordinance, rooftop solar (zones only), trademark search (D-042), brick pricing (D-044).

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex Trojan Horse Arena · Hazel Green area, Madison County, Alabama (site TBD, D-006)	**PHASE 2**	**COVER SHEET SHEET INDEX + DECISIONS**	**NTS**	**October 2026**	**D**	Drawn by KEYSTONE (AI) for Shane Brazelton	**P2-G-001**