HAZEL GREEN HS WRESTLING + FLAG FOOTBALL

New metal training building — PROPOSAL SET REV B

Replaces the old 55' x 45' wrestling room (10' ceiling) at Hazel Green High School, 14380 Hwy 231-431 N, Hazel Green, AL 35750 (Madison County Schools property; location on campus TBD). Supplier: Summertown Metals, 3864 Summertown Hwy, Summertown, TN 38483, (931) 796-1521 (quote TBD).

SHEET INDEX

P1-G-101	Cover + code summary — Rev B (Rev A superseded)
P1-A-201	Floor plan — Rev B (Rev A superseded)
P1-A-301	Elevations + section — Rev B (Rev A superseded)
P1-A-901	3D massing — Rev B (Rev A superseded)

PROJECT DATA (ASSUMED unless cited)

- Building 60' x 125' = 7,500 SF, 1 storey, clear span, 5 x 25' bays, eave 16', 14' min clear, 1:12 gable.
- D-095 (Shane 2026-10-15 5:12 AM CT) supersedes the D-094 layout: restrooms off the corridor; boys wrestling locker room added (ASSUMED — confirm wording); each locker room has its own showers.
- Rooms: wrestling mat room 3,000 SF (42' x 42' mat) · girls' flag football locker 832 SF · boys wrestling locker 832 SF · 2 team shower / WC rooms 364 SF each · women's + men's restrooms 260 SF each · coaches' office 286 SF · storage 143 SF · JAN. / mech 143 SF · 8' N-S + E-W corridors.
- Remodel set (P1-G-001 Rev E, P1-A-101 Rev C, P1-G-002 Rev B) stays the base option.
- Cost: TBD per the Summertown Metals quote + site, foundation, MEP, permit, design. No prices invented.
- Contact: Shane Brazelton, 256-508-4608, brazeltonshane@gmail.com.

CODE SUMMARY — IBC / IPC 2021 (AHJ to confirm)

- Occupancy: A-3 (indoor athletics / training), accessory to Group E campus (ASSUMED).
- Construction: Type IIB (non-combustible PEMB) (ASSUMED).
- Area: A-3 IIB non-sprinklered 9,500 SF / 1 storey allowed (Table 506.2) vs 7,500 SF: PASS.
- Sprinklers: Not required if fire area <= 12,000 SF and load < 300 (903.2.1.3); AHJ / Madison County Schools may require.

OCCUPANT LOAD (IBC 2021 Table 1004.5)

Wrestling mat room	3,000 SF / 50	60
Girls Flag Football Locker Room	832 SF / 50	17
Coaches' Office	286 SF / 150	2
Boys Wrestling Locker Room	832 SF / 50	17
Storage	143 SF / 300	1
Jan. / Mech	143 SF / 300	1
TOTAL (restrooms / showers / corridors accessory)		**98**

EGRESS

- Width: 98 x 0.2 in = 19.6 in needed (1005.3.2) vs 288 in of exit doors (D1-D5): PASS.
- Mat room 60 occ. > 49: 2 exits needed (1006.2.1); 3 provided (D3, D4, corridor I1): PASS. Each locker room 17 occ.: 1 door to the corridor, then 2 directions.
- Travel (Table 1017.2, 200 ft non-sprinklered): worst 94 ft (boys locker far corner to D1, routes ASSUMED): PASS.
- Common path (Table 1006.2.1, 75 ft): worst 52 ft (boys locker far corner to the corridor (2 ways)): PASS.
- Exit doors: panic hardware (1010.2.9); exit signs + egress lighting (1008, 1013).

PLUMBING FIXTURES — IPC 2021 Table 2902.1

Basis: IPC 2021 Table 2902.1 occupancy A-3 (indoor sport facility) ASSUMED; 50 / 50 sex split of the building load (ASSUMED). 98 occ. -> 49 F + 49 M.

FIXTURE	RATIO	REQ.	PROVIDED
WC — female	1:40	2	3 (2 RR + 1 team) PASS
WC — male	1:75	1	2 + 1 UR PASS
Lavatory F / M	1:150 / 1:200	1 / 1	3 / 2 PASS
Drinking fountain	1:1000	1	2 (hi-lo) PASS
Service sink	1	1	1 (JAN.) PASS
Showers	not req. (A-3)	0	8 (4 + 4, 2 acc.) PASS

D-095: every restroom and both team shower / WC rooms have a door on the corridor; the women's / men's restrooms serve the public and visiting teams without entering a locker room.

OPEN ITEMS / FINDINGS

- CONFIRM: second locker room = boys wrestling (ASSUMED from 'boys lockeroom and boys locker room for wrestling'). If Shane meant a separate boys locker room too, a 3rd room needs another bay (60' x 150').
- Team / rosters: girls' flag football 30 + boys wrestling 30 ASSUMED.
- Size 60' x 125' (grown from 60' x 100'): Shane to confirm.
- Location on campus, utilities (water / sewer), geotech: TBD with Madison County Schools.
- Sprinklers / fire alarm: AHJ + district. Supplier quote: Summertown Metals (kit only).

PRELIMINARY — CONCEPTUAL DESIGN — NOT FOR CONSTRUCTION

PROJECT	PHASE	SHEET TITLE	SCALE	DATE	REV	DRAWN BY	SHEET
Hazel Green Regional Athletic Complex **Hazel Green HS · Phase 1 alternate: new metal training building**	**PHASE 1 ALTERNATE**	**COVER + CODE SUMMARY METAL BUILDING (ALT.)**	**NTS**	**October 2026**	**B**	Drawn by KEYSTONE (AI) for Shane Brazelton	**P1-G-101**